



ESTIMATE

Tidewater Home Improvement LLC

Class B Contractor #2705172863

414 Worster Ave

Hampton, Virginia 23669

United States

(757) 551-6413

tidehomepro.com

BILL TO

Mark Northern

Mark Northern

420 Carlisle Rd

Chesapeake, VA

United States

northerncontracting01@gmail.com

Estimate Number: 1421

Estimate Date: September 30, 2026

Valid Until: October 7, 2026

Grand Total (USD): \$5,143.31

- | | |
|---|-------|
| 1. Crawl Space Clean-Up with Insulation Removal — 1 job: full clean-out of the 1,128 sq ft crawl space — the old ground cover, the existing floor insulation, debris and trash are removed and hauled away. | 1 |
| 2. Remove Existing Floor Insulation — 1,128 sq ft: the existing insulation is taken out of the floor joist bays as part of the clean-out. Included at no charge. | 1 |
| 3. New Floor Insulation — 1,128 sq ft: install new R-19 faced batt insulation between the floor joists, secured in place. | 1,128 |
| 4. New Vapor Barrier — 1,128 sq ft: install a new white 10 mil vapor barrier over the crawl space floor, lapped at the piers and perimeter and secured with staples or wire pins. | 1,128 |

Grand Total (USD):

\$5,143.31

Notes / Terms

NOT INCLUDED: any drainage or exterior waterproofing work - no trench drain, no sump pump, no discharge line, no french drain, no exterior grading; no encapsulation, no dehumidifier and no sealing of the crawl space vents; no structural repair - no joist, sill, pier, beam or subfloor repair; no mold or fungus treatment; no electrical work; no plumbing repair; no permits; any work not listed in the scope above.

Notes:

**The work is under the floor - nothing comes up through your floors for the insulation or the vapor barrier.

**Jobsite will be left clean once completed.

**The crawl space is not a storage area during the work - please remove anything you keep down there before we start.

Warranty:

**12 months workmanship on the work performed; the vapor barrier and insulation system is guaranteed against failure of our installation.

Payment Terms:



Total Project Cost: \$5,143.31
Deposit to Schedule: \$2,571.66
Final Payment: \$2,571.65

Check is a preferred method.

**You can pay by credit card using the link below.

<https://request.plastiq.com/pay-tidewater-home-improvement-llc>

Cards not eligible for payment:

- Virtual Affirm credit card

Validity: valid until October 7, 2026.



SCOPE OF WORK

1. Crawl Space Clean-Up with Insulation Removal — 1 job: full clean-out of the 1,128 sq ft crawl space — the old ground cover, the existing floor insulation, debris and trash are removed and hauled away;
2. Remove Existing Floor Insulation — 1,128 sq ft: the existing insulation is taken out of the floor joist bays as part of the clean-out. Included at no charge;
3. New Floor Insulation — 1,128 sq ft: install new R-19 faced batt insulation between the floor joists, secured in place;
4. New Vapor Barrier — 1,128 sq ft: install a new white 10 mil vapor barrier over the crawl space floor, lapped at the piers and perimeter and secured.

JOB DESCRIPTION

Under-floor insulation that has fallen, compressed or stayed wet stops doing its job, and the ground under the house keeps feeding moisture back into it. This estimate takes the old insulation and the old ground cover out with a full crawl space clean-out, then puts the crawl space back together the right way: new R-19 faced batt insulation between the floor joists across the 1,128 sq ft floor, and a new white 10 mil vapor barrier over the ground, lapped and secured, so the floor above stays dry and the new insulation stays dry with it.

View this estimate online: <https://tidewater-est-420-carlisle.pages.dev>